



STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	STP-7318-00(850)		

STRAIN POLE
(PLAN VIEW)
-NOT TO SCALE-



CCTV INSTALLATION ON SAME CORNER
AS SIGNAL CABINET

STRAIN POLE
(PLAN VIEW)
-NOT TO SCALE-



CCTV INSTALLATION ON DIFFERENT CORNER
THAN SIGNAL CABINET

GENERAL NOTES

1. POLE GROUNDING AND LIGHTNING PROTECTION SHALL BE IN ACCORDANCE WITH SECTIONS 639, 647, AND 924 OF THE GEORGIA SPECIFICATIONS.
2. THE CCTV CABINET SHALL BE GROUND MOUNTED AS SHOWN ON THE PLAN SHEETS. IF CABINET LOCATION ON PLANS DIFFERS FROM LOCATION SHOWN ON THIS DETAIL, THE CABINET LOCATION ON THE PLANS SHALL PREVAIL.
3. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL CCTV ASSEMBLY EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE CONTRACT PLANS AND SECTION 936 AND 938 OF THE GEORGIA SPECIFICATIONS.
4. THE CONTRACTOR SHALL FURNISH AND INSTALL NEW SUPPORT/STRAIN POLES IN ACCORDANCE WITH SECTION 639 OF THE GEORGIA SPECIFICATIONS.
5. ALL CABLE ENTRANCES IN OR OUT OF POLE SHALL BE BY A WEATHERHEAD OR RIGID METALLIC CONDUIT BODY WITH A THREADED NIPPLE INSTALLED IN A THREADED COLLAR. THE THREADED COLLAR SHALL BE DESIGNED AND INSTALLED AT THE POINT OF POLE MANUFACTURE. FIELD DRILLING SHALL NOT BE PERMITTED.
6. CONDUITS SHALL BE INSTALLED IN THE FOUNDATIONS OF ALL NEW SUPPORT POLES, INCLUDING LOCATIONS SHOWN IN THE PLANS FOR AERIAL COMMUNICATIONS AND/OR ELECTRICAL POWER SERVICE. IN ADDITION TO THE CONDUITS SHOWN ON THE PLANS, THE CONTRACTOR SHALL INSTALL 2 - 2" AND 2 - 1" (CONDUIT, NONMETAL, TP 2). CONDUITS SHALL BE STUBBED AND CAPPED INSIDE THE CCTV CABINET BASE. ONE 2" AND ONE 1" SHALL REMAIN EMPTY.
7. AERIAL CABLE ATTACHMENT POINTS AND DRIP LOOPS SHALL BE AT LEAST 12" FROM ANY DEVICE OR DEVICE BRACKETS.
8. PULLBOX PB-2, FOR GROUND ROD INSTALLATION, SHALL BE INCLUDED IN THE LUMP SUM BIDDING PRICE FOR CCTV SYSTEM. NO ADDITIONAL PAYMENT SHALL BE MADE FOR PB-2 INSTALLATION.
9. GROUND ROD SHALL BE A MINIMUM OF 6" AND A MAXIMUM OF 10" ABOVE PULL BOX DRAINAGE GRAVEL.



NOT TO SCALE

DATE	REVISIONS	DATE	REVISIONS

CLAYTON COUNTY SPLOST
CCTV INSTALLATION DETAILS
PROJECT - STP-7318-00(850)
DATE SHEET

\$FILES\$
\$DATE\$